

Validate Print Help

**Percentage BoQ**

Tender Inviting Authority: Registrar, IIT Patna

Name of Work: MS framing and Providing and fixing of false ceiling at Workshop 16 C of IIT Patna.

Contract No: IITP/IWD/AZ/11/2022

Name of the Bidder/ Bidding Firm / Company :	
--	--

**PRICE SCHEDULE**  
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	TOTAL AMOUNT including Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7
1	Providing and fixing false ceiling at all heights with integral densified calcium silicate reinforced with fibre and natural filler (galvanized @ 120 grams per sqm including both sides) comprising of main-T runners of size 24x38 mm of length 3000 mm, cross - T of size 24x32 mm of length 1200 mm and secondary intermediate cross-T of size 24x32 mm of (galvanizing @ 80 grams per sqm) i.e. 12x50 mm long dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 76x25x25x1.6 mm fixed with grid and Z cleat of size 25x37x25x1.6mm thick with precut hole on both 25mm flange to pierce into 12x50mm or even bigger size dash fastener if require, fixed with Glavanised iron perimeter wall angle or size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450mm center to center and 40 mm long dry wall S.S screws. The workshall be length 600mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanized mild steel items (galvanizing @ 80 grams per sqm) i.e. 12x50 mm long dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 76x25x25x1.6 mm fixed with grid and Z cleat of size 25x37x25x1.6mm thick with precut hole on both 25mm flange to pierce into 12x50mm or even bigger size dash fastener if require, fixed with Glavanised iron perimeter wall angle or size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450mm center to center and 40 mm long dry wall S.S screws. The workshall be carried out as per specifications, drawing and as per directions of the Engineer-in-Charge.					
1.01	With 15 mm thick Tegular edged light weight calcium silicate false ceiling tiles	37.000	Sqm	1693.65	<b>62665.05</b>	INR Sixty Two Thousand Six Hundred & Sixty Five and Paise Five Only
2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	111.000	kg	78.20	<b>8680.20</b>	INR Eight Thousand Six Hundred & Eighty and Paise Twenty Only
3	Painting with synthetic enamel paint of approved brand and manufacture (Two or more coats on new work)	2.000	Sqm	121.55	<b>243.10</b>	INR Two Hundred & Forty Three and
<b>Total in Figures</b>					<b>71588</b>	INR Seventy One Thousand Five Hundred & Eighty Eight and Paise Thirty Five Only
<b>Quoted Rate in Figures</b>			<b>Select</b>		<b>0.00</b>	INR Zero Only
<b>Quoted Rate in Words</b>			<b>INR Zero Only</b>			